

Document 2024 GW1187

Book 2024 Page 1187 Type 43 001 Pages 17 Date 5/31/2024 Time 2:39:03PM

Rec Amt \$.00

I NDX ANNO SCAN

BRANDY MACUMBER, COUNTY RECORDER MADISON COUNTY 10WA

CHEK

REAL ESTATE TRANSFER - GROUNDWATER HAZARD STATEMENT

TO BE COMPLETED BY TRANSFEROR

If the transaction is exempt from filing a declaration of value pursuant to lowa Code 428A.1(2), <u>STOP HERE</u>. Pursuant to lowa Code section 558.69(1), when no declaration of value is submitted during a transaction, you are not required to submit a groundwater hazard statement or include the statutory language in lowa Code section 558.69(8A). Please consult your realtor or legal counsel for further advice, including on whether a declaration of value is required. The Department provides this information for statutory reference only.

Instruc	ctions for this document can be found at:
Attach	ment 1, if required, can be found at:
Address TRANSF	James Fitzgerald s: 2808 W Ave, Parnell, IA 52325
Address	s: 2608 120th Street, Van Meter, IA 50261
2608 120 Legal Des	of Property Transferred: th Street, Van Meter, Iowa 50261 scription of Property: (Attach if necessary)
(77) Nortl	" located in the Northwest Quarter (1/4) of the Northwest Quarter (1/4) of Section Fourteen (14), Township Seventy-seven h, Range Twenty-seven (27) West of the 5th P.M., Madison County, Iowa, as shown in Amended Plat of Survey filed in Book 190 on July 8, 1998 in the Office of the Recorder of Madison County, Iowa.
1. Wel	Is (check one) No Condition - There are no known wells situated on this property.
2. Solid	Condition Present - There is a well or wells situated on this property. The type(s), location(s) and legal status are stated below or set forth on an attached separate sheet, as necessary. Closed and not in USC - was not in uSe at any point during our ownership waste Disposal (check one) No Condition - There is no known solid waste disposal site on this property. Condition Present - There is a solid waste disposal site on this property and information related thereto is provided in Attachment #1, attached to this document.

February 15, 2023 FILE WITH RECORDER DNR Form 542-0960

3. Hazardous Wastes (check one)

	No Condition - There is no known hazardous waste on this property. Condition Present - There is hazardous waste on this property and information related thereto is provided in Attachment #1, attached to this document.
4. Und	erground Storage Tanks (check one) No Condition - There are no known underground storage tanks on this property. (Note exclusions such as small farm and
	residential motor fuel tanks, most heating oil tanks, cisterns and septic tanks, in instructions.) Condition Present - There is an underground storage tank on this property. The type(s), size(s) and any known substance(s) contained are listed below or on an attached separate sheet, as necessary.
5. Priva	ate Burial Site (check one)
	No Condition - There are no known private burial sites on this property. Condition Present - There is a private burial site on this property. The location(s) of the site(s) and known identifying information of the decedent(s) is stated below or on an attached separate sheet, as necessary.
	ite Sewage Disposal System (check one)
	No Condition - All buildings on this property are served by a public or semi-public sewage disposal system. No Condition - This transaction does not involve the transfer of any building which has or is required by law to have a
A	sewage disposal system. Condition Present - There is a building served by private sewage disposal system on this property or a building without any lawful sewage disposal system. A certified inspector's report is attached which documents the condition of the private sewage disposal system and whether any modifications are required to conform to standards adopted by the
	Department of Natural Resources. A certified inspection report must be accompanied by this form when recording. Condition Present - There is a building served by private sewage disposal system on this property. Weather or other temporary physical conditions prevent the certified inspection of the private sewage disposal system from being conducted. The buyer has executed a binding acknowledgment with the county board of health to conduct a certified inspection of the private sewage disposal system at the earliest practicable time and to be responsible for any required modifications to the private sewage disposal system as identified by the certified inspection. A copy of the binding
	acknowledgment is attached to this form. Condition Present - There is a building served by private sewage disposal system on this property. The system is failing to ensure effective wastewater treatment or is otherwise improperly functioning, and the buyer has executed a binding acknowledgment with the county board of health to install a new private sewage disposal system on this property
	within an agreed upon time period. A copy of the binding acknowledgment is provided with this form. Condition Present - There is a building served by private sewage disposal system on this property. The building to which the sewage disposal system is connected will be demolished without being occupied. The buyer has executed a binding acknowledgment with the county board of health to demolish the building within an agreed upon time period. A copy of the binding acknowledgment is provided with this form. [Exemption #7]
	Condition Present - There is a building served by private sewage disposal system on this property. This property is exempt from the private sewage disposal inspection requirements pursuant to the following Exemption [Note: for exemption #7 use prior check box]:
	Condition Present - There is a building served by private sewage disposal system on this property. The private sewage disposal system has been installed within the past two years pursuant to permit number:
	

Review the following two directions carefully:

A. If you selected a box stating "No Condition" for every numbered section above, <u>STOP HERE</u>. Do not submit this form. Instead, pursuant to lowa Code section 558.69(8A), you must include the following language on the first page of the recorded deed, instrument, or other writing:

February 15, 2023 FILE WITH RECORDER DNR Form 542-0960

"There is no known private burial site, well, solid waste disposal site, underground storage tank, hazardous waste, or private sewage disposal system on the property as described in Iowa Code section 558.69, and therefore the transaction is exempt from the requirement to submit a groundwater hazard statement."

Please consult your realtor or legal counsel for further advice on this exemption. By law, the owner of the property is responsible for the accuracy of this statement, and the Department provides this information for statutory reference only.

B. If you checked <u>any</u> box stating "Condition Present" for <u>any</u> of the numbered sections above, continue below. You must complete this form, including providing all required information, and you must submit this form to the county recorder's office with declaration of value.

	tion required	by stateme	ents check has	ed above :	should be	e provi	ded here ∪S<	e or on	separa any	te sheets	attached i	nereto:
ow,	nership						 			J		
· · · · ·									· · ·			
						<u>"</u>						
	DECLARE THA		REVIEWE	D THE IN	STRUCTI	ONS F	OR THIS	S FORM	∕I AND	THAT TH	IE INFORN	NATION STATE
Signature:	TRUE AND C	(Transferor)	Ec		Tele	ephone	No.:	5/5-2	201-1	180		

GROUNDWATER HAZARD STATEMENT

ATTACHMENT #1

	NOTICE OF WASTE DISPOSAL SITE
a. Solid Waste D	isposal (check one)
☐ There is a	solid waste disposal site on this property, but no notice has been received from the Department of Natural
Resources	s that the site is deemed to be potentially hazardous.
☐ There is a	solid waste disposal site on this property which has been deemed to be potentially hazardous by the Department of
Natural Re	esources. The location(s) of the site(s) is stated below or on an attached separate sheet, as necessary.
o. Hazardous W	estes (check one)
☐ There is h	azardous waste on this property and it is being managed in accordance with Department of Natural Resources rules.
☐ There is h	azardous waste on this property and the appropriate response or remediation actions, or the need therefore, have
,	en determined.

Further descriptive information:

I HEREBY DECLARE THAT I HAVE REVIEWED THE INSTRUCTIONS FOR THIS FORM AND THAT THE INFORMATION STATED ABOVE IS TRUE AND CORRECT.



DIRECTOR KAYLA LYON

TIME OF TRANSFER INSPECTION TOT# 10108 GARY WELKER CERT # 12732

-Site Information -

Parcel Description: 111021444002000

Address: 2608 120th Street, Van Meter, IA 50261

County: Madison

Owner Information

Property is owned by a business: No

Business Name:

Owner Name: James Fitzgerald

Email Address: armfitzgerald@protonmail.com Address: 2608 120th Street, Van Meter, IA 50261

Phone No: 515-231-8318

Site related information-

No Of Bedrooms: 3

Facility Type: Residential

Last Occupied:

Permit issued by County: N/A

All plumbing fixtures enter septic system: Yes

Property Information Comments:

Inspection Date: 05/07/2024

Currently Occupied: Yes

System Installation Date:

Permit Number:

County contacted for records: Yes

Primary Treatment

Tank 1

Tank Name: Tank 1

Tank Material: Plastic

No. of Compartments: 1

Date Pumped: 5/7/2024

Distance To Well (Ft.):

Risers Intact: Yes

Type: Septic Tank

Is Accessible: Yes

Tank Corrosion Type: None

Pump Tank Chamber: No

Meets Setback to Well: N/A

Effluent Filter Present: No

Tank Size (Gal): 1250

Liquid Level Type: Normal

Licensed Pumper Name: Bob's Septic

Well Type:

Lid Intact: Yes

Watertight: Yes

Tank/Vault Pumped: Yes

Inlet Baffle Present: Yes

Outlet Baffle Present: Yes

Functioning as Designed: Yes

Tank Comments:

General Primary Treatment Comments:

Distribution Type

Distribution Box 1

Label: Distribution Box 1

Box Opened: Yes

Watertight: Yes

Material Type: Plastic

Baffle Present: Yes

Functioning As Designed: Yes

Accessible: No

Speed Levelers Present: Yes

General Distribution System Comments:

Secondary Treatment

Lateral Field1

Distribution Type: Distribution Box

Lines: 5

Gallons Loaded: **350**Distance To Well (Ft.):

Grass Cover Present: Yes

Easement Present: N/A

Comments:

Material Type: Gravelless Pipe

Total Length of Absorption Line: 500

Meets Setback to Well: N/A

Lateral Lines Probed: Yes

Lateral Lines Equal Length: Yes

Functioning as Designed: Yes

Trench Width: 24

System Hydraulic Loaded: Yes

Well Type:


Saturation or Ponding Present: No

System Located on Owner Property: Yes

General Secondary Treatment Comments:

Narrative Report-

TOT Inspection Report Overall Narrative Comments: Upon arrival client showed us location of 3 septic tank lids. One above outlet of primary 1250gallon septic tank and the other two were to the secondary 750gallon septic tank. Removed inspection ports from all 3 lids, and seemed to be riveted to risers; to prevent damage did not pull lids off and inspected through ports. The inlet baffle to the 750g tank is currently broken but not causing the septic tank to break in anyway or not be watertight. Used map and probe to locate distribution box and lateral lines. Excavated approx. 1ft down to dbox. Hydraulic load tested with 350g of water. All lateral lines took evenly during test. Pumped all waste from tanks. Placed all lids back in positions and concluded the time of transfer. Information is current at the time of the inspection.



DIRECTOR KAYLA LYON

TIME OF TRANSFER INSPECTION TOT# 10108 GARY WELKER CERT # 12732

Owner Name:

James Fitzgerald

Address:

2608 120th Street , Van Meter , IA 50261

County:

Madison

Inspection Date:

05/07/2024

Submitted Date:

5/15/2024


This page certifies a Time of Transfer inspection was conducted and submitted for the property listed above in accordance with Subrule 567 IAC 69.2(8).


5/15/2024 10:47:08 AM


Page: 3 of 6


DNR Form 542-0191

- Documents -













Madison County Office of Zoning and **Environmental Health** Authorization to Construct a Private On-site Wastewater

112 N. John Wayne Drive P.O. Box 152

Winterset, IA 50273-0152

Treatment System (POWTS)

Telephone: (515) 462-2636

Permit Number:

133-04

Date Issued: October 8, 2004

Issued to:

John & Brigetta Hughes

Address:

2608 - 120th Street

Van Meter, Iowa 50261

Legal Description:

PARCEL B 4.9.4 NW CORNER NW NW Section 14 T77 R27 Jefferson Twp

POWTS Components Specifications: 2000 gal septic tank - EQ24 5 @ 100'

General Conditions:

- 1. System must be constructed in conformance with attached system layout, profiles, and cross-sections.
- 2. Structures must be constructed in conformance with 567 IAC Chapter 69 and the Madison County Environmental Health Regulations.
- 3. Permit shall be null and void if system is not constructed within one year of permit issuance. The Environmental Health Officer must approve any request for extension of permit.
- 4. The Environmental Health Officer must approve any design modifications to the permitted system prior to construction.
- 5. Once constructed, all system components must be uncovered for inspection and the system must be approved before it can be put into operation. Notice for inspection must be received with 24 hours in advance (8 a.m. through 4:30 p.m., Monday - Friday). If weather necessitates the need to cover the system components, then the system owner or contractor must notify and follow the procedures given by the Environmental Health Officer.

Special Conditions:

Environmental Health Officer

Madison County

Office of Zoning and Environmental Health

Madison County Office of Zoning & Environmental Health

Application to Construct Private On-Site Wastewater Treatment System (POWTS)

112 N. John Wayne Dr. P O Box 152 Winterset, IA 50273 Telephone (515) 462-2636

Office Use Only				Temp E911:		· · · · · · · · · · · · · · · · · · ·	
Tracking No.		Fee Paid	Date Issued	Date Inspected	Date Approved :	Section/Township	NPDES Authorization #
133-04	10-8-04	P150	10-8-04	,		* 1	· [

Application will not be accepted until site and soil analysis/percolation information, and two diagrams of the system layout, profiles and cross-sections have been received; and fee has been paid. For systems requiring an NPDES General Permit #4 (surface discharge), its application must be submitted to this office and appropriate forms recorded before a permit will be issued.

Please Print All Informati	tion.				
1. Owner Information (Application)	ast)		2. Contractor Informa	tion	
First Name	Last Name		First Name	Last Name	
John	Hughes		Grea	Mages	1
Address	0		Address	1164	
2408 1201/2 City	. St. IA.	50361	Van Meter	JA (John 5) State	5026 1 Zip
Van Meter		,	City 290 8 (515) 996-243 Phone Number (area cod		Zip
Phone Number (area code) (515) 996 - 2517	Fax or E-mail Co	ell Phone	Phone Number (area cod	e) Fax or E-mail	Cell Phone
3. System Requirement Inform	astion		4. Site and Soil Evalua	tor (Percolation Test)	
IAC CHAPTER 69 DOUBL		NK REQUIRED ink Size Required		ST MUST BE COMPLETE TO THE ISSUANCE OF P	ED AND APPROVED PRIOR ERMIT
1-3 Bedroom		•	Data tast talian	Task kalisan har	1
		1250	Date test taken	rest taken by	3
4 Bedroom		1250	l'est Kesults: Hoi	e l min/in Hole	2 min/in
5 Bedroom		1500	Ho	le 3 min/in Hol	e 4 min/in
6 Bedroom		1750	Averagemin	/in Depth of Test Ho	les
			Number of Laterals	s Required	
			Length of Laterals	Required	ft. ea
5. Type of Submittal	6.Address Information	va		10 - 11	
☑ New	Location, Number &	: Street of project (if	unknown, indicate near	est road):	27.
Revision	Legal Description:				
Repair, Tank		ハイー フワー	,27		!
Repair, Treatment Area	· ·	•	•		1. 1
System Replacement	1	ircel B	4.9 A Nh	J Gorner Nu	I NW
Previous Permit #:					
7. Type of Building (Complete	d by Owner)				
☑ Residential	Number of Bedro	oms: 4	☐ Commercial/Other	Non-Residential Use:	
Other buildings served by this sys	stem	•	Garbage Disposal		
Hone				Annliance (i.e. whiringol has	
THE				reprisince (i.e. willipool out	h water softener) Oto:
B .					h, water softener) Qty:
			omplete the remaining p	ortion of this application.	
8. Primary and/or	Type Plastic	Manufacturer:	omplete the remaining p	ortion of this application.	Size (gal): 3000
Mechanical Trentment			omplete the remaining p	ortion of this application.	
Mechanical Treatment 9. Pump/Siphon Not Applicable	Type: Flastic Type Type:	Manufacturer: Manufacturer: Manufacturer:	omplete the remaining p	ortion of this application. lel:	Size (gal): 3000
Mechanical Treatment 9. Pump/Siphon Not Applicable 10. Secondary Treatment Are	Type: Flastic Type Type: Type:	Manufacturer: Manufacturer: Manufacturer:	omplete the remaining p	ortion of this application. lel: lel:	Size (gal): 3000 Size (gal):
Mechanical Treatment 9. Pump/Siphon Not Applicable	Type: Flastic Type Type: Type:	Manufacturer: Manufacturer: Manufacturer:	omplete the remaining p	ortion of this application. lel:	Size (gal): 3000 Size (gal): Dosing Frequency:
Mechanical Treatment 9. Pump/Siphon Not Applicable 10. Secondary Treatment Are	Type: Flastic Type Type: Type:	Manufacturer: Manufacturer: Manufacturer:	omplete the remaining p	ortion of this application. lel: lel:	Size (gal): 3000 Size (gal):
Mechanical Treatment 9. Pump/Siphon Not Applicable 10. Secondary Treatment Are Type of Laterals C. 24 I hereby attest the truth an Request for inspection of the distribution box must filter and must be covered County Recorders Office.	Type: Flastic Type: Type: a Type: mber of Laterals Le 5 nd accuracy of all facts the system must be mad t be available. Mechani by a maintenance agre	Manufacturer: Manufacturer: Manufacturer: Not Applicabength of ca. Lateral ///// and information ple 24 hours in advaical systems requiement, which musnical systems and	omplete the remaining p office Mod Mod Mod Mod Mod Mod Mod Mod	ortion of this application. lel: lel: Cother Cother Ication. to test is sand ladison reconstruction prior to issua	Size (gal): 2000 Size (gal): Dosing Frequency: Maximum Trench Depth

MC-ZELL form EH01

RLI1002 PID 111021444002000 00 Tax Dist 111 000 Class A INQUIRY

2004 061 Map# 000000314100007 GIS#

. . . .

Property 002954800 DED Hughes, John & Brigetta

Ownership

2608 120Th St

Van Meter IA 50261-

000000000

Location 2608 Street 120TH ST City VAN METER

Rec REC 139 332

Doc

Misc Exempt Code No Ag Cr VIN#

Sec-Twp-Rng 014 077 027 Cty-Adn-Blk 00014 Title

Legal Desc PARCEL B 4.94A NW CORNER NW NW

Applications Typ 1 AGL Ovr Amt 1,600 Typ 2 H ... Ovr Amt

Typ 3 Ovr Amt Typ 4 ... Ovr Amt

			Acres	Тур	Desc	Value	Rollback	Acres
	100%	Rollback Gr	4.94	LND	Land	1,600	1,600	4.55
Grs	78,000	39,239 Ex	.39	DWL	Ag Dwlg	75,200	36,439	
Mil		PE	.00	BLD	Bldgs	1,200	1,200	
Net	78,000	39,239 Dr	.00	EXM	Exempt			.39
		Net	4.55					

F3=Exit F10=Ownership F12=Prev F13=Rec Doc F14=Image F15=Legal F16=IE F17=Notes F18=TaxHist F19=Aplc F20=Value F21=Print F22=View Image F23=Indexing Date taken: 10-4-04

By: Jim Vance

Owner: John & Bergetta Hughes

Site Address: 2608 - 120th St Phone No. 996-2517

Lot Size: 5 ac. Legal Description: Parcel "B" in the NW. 4 of the NW. 4 of Sec. 14-77N-R27W

Structure: New X Existing # Bedrooms: Installer:

Owner's Current Mailing Address: 2608 120th St. Van Meter, Iowa 50261

Time for 1 inch of water: 1. 15.0 min Depth of holes tested:

1. 36"

2. <u>18.5 min</u>

3. <u>17.1</u> min

4. 16.0 min 36"


Results of 6 foot hole: No Rock No Water

Min. recommended lateral footage per IAC Ch. 69: 500 feet

Drawing of perc site below.

Number of laterals required: 5 each

Average length of laterals: ___100 feet





I hereby certify that this engineering document was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of lowa.

Warlest Vance

Date: 5 Oct. 2004 Reg. No. 5041 Exp. Date: 31 Dec. 2005

Permit No 133-04 Name: Hughes 911 Sign Locate
Date of Inspection: 10/26/04 Inspected by: Elton Root
Contractor: M&M Construction
Dwelling under construction or moved in Yes No No
Setbacks
Meets required setbacks.
• Rural Water Yes No
 Private wells/Groundwater heat pump bore holes/suction water lines/lakes Outside required 50-foot setback for tank Yes ∑ No
Outside required 100-foot setback for laterals Yes \(\sigma \)
. Streams/ponds (25-25 ft)-ditches (10-10 ft) Yes No
Indications of water lines under pressure Yes No
Comments:
,
Building Sewer
• Clean outs – one right outside of house Yes ⊠ No □
• location of cleanout inside house and set requirement
• Pipe is sch 40 and has a 4-inch diameter. Yes ⊠ No □
• Grade – has adequate fall. Yes ⊠ No □
Comments:
Tank Tank. Manufacture Xactic Concrete Plastic Plast
• Capacity 1250 & 750 -gallon
• Two compartments, both meet the specs for capacity. Yes⊠ No □
Baffle Yes ☑ No ☐
 Inlet/Outlet tees are ok. Yes ∑ No □
• Effluent filter in the outlet. Yes ⊠ No ☐ Manuf.Tuf-Tite
Tank depth.10 inches
• Risers Yes No
• Lids above grade screwed on Yes No Will be
Comments:
Distribution Box
• Brand Tuf-Tite Other
Bedded in cement. Yes⊠ No Will be
 Has required inlet baffle. Yes∑ No☐ Will be☐
• Outlet levels −are level. Yes No Unknown
Comments:
Laterals Distribution lines A inch DVC sine SCU25
 Distribution lines: 4-inch PVC pipe – SCH35 Distribution lines screwed to laterals. Yes No Will be
• Lateral used. ADS 24 Reduction? Yes No
• Lateral depth 24 inches Perc depth 36 inches
• Laterals were level. Yes⊠ No□
Adequate amount of undisturbed soil between laterals. Yes № No
• Distance 7 feet between laterals.
Comments:





Permit # 133-04 Hushes Inspection 10/26/04